GOVERNMENT OF ASSAM
OFFICE OF THE CHIEF ENGINEER, P.W.D. (ROADS), GUWAHATI-03

NOTIFICATION: SCHEDULE OF RATES FOR BRIDGE WORKS 2025-2026
Circular No. CE/PWD(R)/SOR/2025/114 Dated: 15-01-2025

1. SCOPE AND JURISDICTION:
This Schedule of Rates (SOR-2025) is applicable for all Highway, River Bridge, and Flyover construction projects under Assam State Roads Project, PWRD Guwahati, Dibrugarh, Silchar, and Tezpur circles.

2. SCHEDULE OF ITEMS AND APPROVED RATES:

Item 1.01: Structural Concrete in Superstructure (M35 Grade)
Providing, batching, mixing in computerized batching plant, transit mixer carriage, pumping, vibrator compaction, and steam/water curing for 14 days in bridge deck slab, longitudinal T-beams, and cross girders:
- Approved Rate: Rs. 8,650.00 per cubic metre (m3)

Item 1.02: High-Performance Concrete (M40 / M45 Grade)
For long-span river bridges (>30m span) and precast segmental girders:
- Approved Rate: Rs. 9,450.00 per cubic metre (m3)

Item 2.01: Reinforcement Steel (Fe 500D TMT Bars)
Conforming to IS 1786 Grade Fe500D (high ductility), including decoiling, straightening, cutting, bending, binding wire, and hoisting in position at all heights:
- Approved Rate: Rs. 86,500.00 per metric tonne (tonne)

Item 3.01: Bored Cast-in-Situ RCC Piles (1000mm Diameter)
Boring in all types of riverbed alluvial soils, sand, clay, silt, and soft rock strata including casing pipe, bentonite slurry circulation, and cleaning:
- Approved Rate: Rs. 4,550.00 per linear metre (m)

Item 4.01: Centering and Shuttering (MoRTH Section 1500)
Steel formwork with staging across riverbeds including striking and scaffolding:
- Approved Rate: Rs. 820.00 per square metre (m2)

3. SEISMIC AND QUALITY PROVISIONS:
As Assam falls in Seismic Zone V, all bridge piers must strictly incorporate ductile confining stirrups per IRC:112 with 135-degree seismic hooks and 10d extension.